

API NUMBER 15-071-20363-00-00

LEASE NAME Edsall 'F'

WELL NUMBER 3

330 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 1 TWP. 16S RGE. 43 (X) or (W)

COUNTY Greeley

Date Well Completed 6/5/85

Plugging Commenced 3/29/93

Plugging Completed 4/14/93

TYPE OR PRINT

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

CONSERVATION DIVISION  
 LEASE OPERATOR Marathon Oil Company

ADDRESS P.O. Box 2690, Cody, WY 82414

PHONE# (307) 587-4961 OPERATORS LICENSE NO. 30689

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Approx. March 23-24, 1993 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? --

Producing Formation Morrow Depth to Top 5125' Bottom 5164' T.D. 5280'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Oil, Water, Gas	Surface	475'	8-5/8"	0'-475'	None
		Surface	5278'	4-1/2"	0'-5278'	640'-0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set cement retainer at 5051'. Squeezed Morrow perms 5125'-5164' with 40 sxs. cement. Stung out of retainer and left 1 bbl. cement on top of retainer. Set cement plug #1 from 3955'-2767' (120 sxs.). Set cement plug #2 from 2767'-2275' (50 sxs.). Cut casing at 902'-could not pull. Cut casing at 640' & POOH. Set tubing at 707' & pumped 125 sxs. cement plug to 275'. (Over)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gibson Well Service License No. 5866

Address Cheyenne Wells, CO

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Marathon Oil Company

STATE OF Wyoming COUNTY OF Park, ss.


R.P. Meabon (Regulatory Coordinator) (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R.P. Meabon

(Address) P.O. Box 2690, Cody, WY 82414

SUBSCRIBED AND SWORN TO before me this 27<sup>th</sup> day of May, 19 93

Connie A. Shwartz  
 Notary Public



My Commission Expires: 9-6-1996

Plugging Record (Cont.)

Set 10 sxs. cement plug from 30' to surface. Dug down surface pipe to 4'  
Welded on cap with the following information:

Edsall F-3  
Section 1, T16S, R43W  
Greeley County, Kansas  
14-APR-93