

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67702

WELL PLUGGING RECORD
K.A.R. -82-3-117

API NUMBER 15-071-20390-00-00

Lease Name Edsall F

WELL NUMBER 7

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 1 TWP. 16S RGE. 43W (E) or (W)

COUNTY Groecley

Date well completed 9/28/85

Plugging Commenced 9/28/99

Plugging completed 9/28/99

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Herman L. Loeb

Address P. O. Box 524 Lawrenceville, IL 62439

Phone (618) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Oil

Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/2/99 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? yes If not, IS well log attached? no

Producing Formation Morrow Depth to Top 5116' Bottom 5131' T.D. 5300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>5116</u>	<u>5131</u>	<u>8 5/8"</u>	<u>476'</u>	<u>0'</u>
				<u>4 1/2"</u>	<u>5300</u>	<u>0'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Tubing parted, top of tubing at 3200'. RIH w/ tubing & packer, set packer @ 2452'. Pressure test annulus to 400 psi, holds ok. Pump 50 sk of cement followed by 50 sk w/ hulls, displace to below packer. POH w/ tubing & packer. Set cast iron bridge plug @ 2000'. Perforate @ 1550'. Top of cement @ 1800' (cement bond log). RIH w/ tubing to 1520'. Pump 90 sk cement, pull tubing to 360', pump 20 sk to circulate cement to surface. POH w/ tubing Pump 70 sk down 4 1/2" casing. Pump 100 sk down annulus. Top off 4 1/2" w/ 50 sk. Use 60/40 poz mix w/ 6% gel.

Name of Plugging Contractor Mull Drilling License No. 5144

Address P O Box 2758 Wichita, KS 67201-2758

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.

George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) 7588 Marywood Drive Newburgh, IN 47630

Subscribed and sworn to before me this 12th day of October, 19 99

Donna Carlene Lucas
Notary Public

My commission expires: April 6, 2002
STATE CORPORATION COMMISSION

RECEIVED
OCT 12 1999
10-12-1999
CONSERVATION DIVISION
Wichita Kansas

"OFFICIAL SEAL"
DONNA CARLENE LUCAS
Notary Public, State of Illinois
My Commission Expires: 4/6/02

FORM CP-4
1