

AMENDED

TYPE OR PRINT
 NOTICE: Fill out completely and return
 to Cons. Div. office within 30 days.

API NUMBER 15-203-20037-00-00
 LEASE NAME Caldwell "C"
 WELL NUMBER 2
740 Ft. from S/E Line of Section (circle one)
1831 Ft. from N/W Line of Section (circle one)
 SPOT LOCATION SE - NW - SE - SW
 SEC. 34 TWP. 20 S. RGE 38 (E) or (W)
 COUNTY Wichita
 Date Well Completed 1976
 Date Plugging Commenced 3/3/97
 Date Plugging Completed 3/4/97

LEASE OPERATOR Kaiser-Francis Oil Company
 ADDRESS P. O. Box 21468
 CITY, STATE, ZIP Tulsa, OK 74121-1468
 PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568
 Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)
 by Kevin Strube (KCC District Agent's Name)

Is ACO-1 filed? On old form not, is well log attached? -
 Producing Formation(s) Morrow Depth to Top 4774 Bottom 4876 T.D. 4950

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Morrow	Oil	4774	4876	8 5/8	342	-0-
				4 1/2	4950	1805

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Dumped 4 sxs cmt on top of CIBP. Ran free-point & cut off 4 1/2" casing @ 1805'. Pumped 50 sxs 60/40 poz + 500# hulls. Pulled casing up hole to 1200' & pumped 80 sxs cmt. Pulled csg up to 675' & pumped 35 sxs cmt. Pulled up to 375' & pumped 40 sxs cmt. Circ'd to surf. Topped off w/15 sxs cmt. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mike's Testing & Salvage, Inc.
 License No. 31529
 Address P. O.Box 467, Chase, KS 67524
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company
 STATE OF Oklahoma COUNTY OF Tulsa, ss.

03-31-97
 RECEIVED
 KANSAS CORP COMM
 APR 31 P 12:32

Charlotte Van Valkenburg (Employee of Operator or (Operator) of above-described well, being first
 duly
 sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg
 (Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 28th day of March, 19 97

[Signature]
 Notary Public
 My Commission Expires: 10-4-99