

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-203-20,1230000

LEASE NAME Caldwell "C"

WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

740 Ft. from (S) Line of Section (circle one)

2000 Ft. from (W) Line of Section (circle one)

EASE OPERATOR Kaiser-Francis Oil Company

SPOT LOCATION SW - NE - SE - SW

ADDRESS P. O. Box 21468

SEC. 34 TWP. 20 S. RGE 38 (E) or (W)

CITY, STATE, ZIP Tulsa, OK 74121-1468

COUNTY Wichita

PHONE#(918) 491-4314 OPERATORS LICENSE NO. 6568

Date Well Completed 12/3/96

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 12/3/96

Date Plugging Completed 12/3/96

The plugging proposal was approved on 12/3/96 (date)

by Steve Middleton (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation(s) None Depth to Top - Bottom - T.D. 5000

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
None	Dry	-	-	8 5/8	273	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Spotted cmt plugs as follows: (1) 50 sxs 60/40 poz @ 2275', (2) 80 sxs 60/40 poz @ 1120', (3) 40 sxs 60/40 poz @ 675', (4) 50 sxs 60/40 poz @ 300' & (5) 10 sxs 60/40 poz @ 40'. (Pumped 15 sxs cmt in rathole & 10 sxs cmt in mousehole). Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Co., Inc.

RECEIVED  
STATE CORPORATION COMMISSION

License No. n/a

JAN 21 1997

Address 250 N. Water St., Ste. 300, Wichita, KS 67202-1299

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator or (Operator) of above-described well, being first

sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Jan Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 15th day of January, 19 97

Debra L. Fields  
Notary Public  
My Commission Expires: April 27, 1999