

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
30 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-203-20050 - 00-00

LEASE NAME ZODY

WELL NUMBER B-1

1390 Ft. from N Section Line

1390 Ft. from W Section Line

SEC. 34 TWP. 20S RGE. 38 ( X ) or ( W )

COUNTY WICHITA

Date Well Completed 3-9-91

Plugging Commenced 4-6-02

Plugging Completed 4-6-02

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

RECEIVED  
05-20-02  
MAY 20 2002

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # ( 806 ) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-1-02 (date)

by KEVIN STRUBE KCC WICHITA (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation COUNCIL GROVE Depth to Top 2905 Bottom 2986 T.D. 3070

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
COUNCIL GROVE	GAS	2905	2986	8 5/8	530	0
				4 1/2	3053	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. PUMP 3 SXS HULLS & 20 SXS CMT DOWN CSG. PMP 24 BBLs 9PPG MUD. PUMP 95 SXS CMT FROM 1200 TO SURF. PUMP 30 SXS CMT DOWN ANNULUS FROM 120 TO SURFACE. PRESSURE TEST TO 400. CUT OFF AND CAP 8 5/8 AND 4 1/2 CSG 3' BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 498A, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF TEXAS COUNTY OF POTTER, ss.  
CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Craig R. Walters  
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER

(Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101



SUBSCRIBED AND SWORN TO before me this 16 day of May, 2002

Lori Pearson  
Notary Public

My Commission Expires: 2/26/05

CP