

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-203-30055-000

LEASE NAME Caldwell (OWWO)

WELL NUMBER #1

SPOT LOCATION C-SE-SE

SEC. 33 TWP. 20 RGE. 38 (E) or (W)

COUNTY Wichita

Date Well Completed 8-24-67

Plugging Commenced 1-27-86

Plugging Completed 2-13-86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Jon Carroll Oil

ADDRESS Box 1987, Great Bend, Kansas 67530

PHONE # (316-793-7156) OPERATORS LICENSE NO. 5921

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One (1)

Is ACO-1 filed? If not, is well log attached? Not available

Producing formation Depth to top bottom T.D. 5137'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	306'	None
				4-1/2"	5133'	1,094.59'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 4900' and 4 sacks cement. Shot casing at 2500', 1500' and 1100'. Pulled 33 joints of 4-1/2" casing. Allied squeezed well with 3 sacks hulls, 50 sacks cement, 15 sacks gel, released plug and pumped 200 sacks 60/40 pozmix cement with 6% added gel. Maximum pressure was 700 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 14th day of February, 1986

IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

My Commission expires:

Notary Public
FEB 10 1986