


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-203-00006-00-00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Wichita County, Sec. 32 Twp. 20 Rge. 38 (E) W (W)

Location as "NE/CNW\*SW\*" or footage from lines SW SW NE  
Lease Owner B & R Drilling, Inc.  
Lease Name Barbro Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 9/23/52 19  
Application for plugging filed 9/21/52 19  
Application for plugging approved 9/21/52 19  
Plugging commenced 9/22/52 19  
Plugging completed 9/22/52 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5100 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	210	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGING RECORD

Layed down drill pipe, set first plug at 210' with 20 sacks of cement. Filled hole with rotary mud to 35', set plug at 35', 1/2 sack hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr.  
Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 19 52

My commission expires 6-17-54.

Clare Hammer  
Notary Public.

24-2675-B 2-52-20M

DEC 22 20 2824  
17 24

10-01-52  
CONSERVATION DIVISION  
Wichita, Kansas

15 20300006-0000

B & R Drilling, Inc.  
Dwbro #1

SW SW NE 32-20-38  
Wichita County, Kans.

Total Depth: 5100'  
Comm. 8/26/52  
Comp. 9/23/52

Casing

Cement

8 5/8" Set 210'

150 sacks Bulk

Formation	Depth
Surface clay-sand-rock	40
Shale	80
Sand	95
Sand-shell	200
Shale-shell	210
Shale-sand	600
Shale-shell	740
Sand	770
Shale-shell	1250
Shale-shells-red bed	1640
Anhydrite	1660
Anhydrite-shale	1740
Salt-shale-red bed	2020
Shale-shells	2100
Red bed-shale-shells	2250
Shale-red bed	2360
Anhydrite-shale	2400
Sandy shale	2670
Shale-lime-shells	2765
Lime-shale	4175
Lime	4893
Lime-shale	4920
Lime	4945
Lime-sand	4970
Lime-shale	5043
Lime	5100'

STATE OF KANSAS )  
                          ) ss  
RUSSELL COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.

*Caro Dief*  
-----

Subscribed and sworn to before me this 29th day of September, 1952.

*Wesley Edmund*  
-----  
Notary Public

My commission expires: 6-17-54.

**PLUGGING**  
FILE SEC 32 T 20 R 3124  
BOOK PAGE 47 LINE 34