

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

*John Meyer*

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

API NUMBER 15-203-20053-00  
LEASE NAME Collingwood Estates  
WELL NUMBER 1  
SPOT LOCATION \_\_\_\_\_  
SEC. 28 TWP. 20 RGE. 38 (E) or (W) (W)  
COUNTY Wichita  
Date Well Completed 8-3-81  
Plugging Commenced 7-23-84  
Plugging Completed 7-23-84

LEASE OPERATOR Intercep Resources, Inc.  
ADDRESS Box 2470 Del Mar CA. 92014  
PHONE (619) 481-2375 OPERATORS LICENSE NO. 6506

Character of Well Gas  
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes  
Which KCC/KDHE Joint Office did you notify? Dodge City, ks.  
Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Council Grove Depth to top 3026 bottom 3098 T.D. 3258

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS 1 CASING RECORD \_\_\_\_\_

Formation	Content	From	To	Size	Put In	Pulled out
<u>Council Grove</u>	<u>Gas. Water</u>	<u>0</u>	<u>415</u>	<u>8 5/8</u>	<u>415</u>	<u>None Cemented</u>
		<u>0</u>	<u>3247</u>	<u>5 1/2</u>	<u>3247</u>	<u>None Cemented</u>
						<u>from top to</u>
						<u>bottom both</u>
						<u>strings.</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Halliburton Liberal, ks. Pumped 25 SX 60-40 27% gel 3% CC - 10 SX gel - 50 SX 60-40 27% gel 3% CC. 5 SX gel. 100 SX 60-40 2% gel 3% CC. Filled to 300' of surface. Will fill to top when we plug Collingwood Estates #3 in August.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Liberal, ks License No. 5287  
Address Liberal, ks.

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Ks COUNTY OF JewarD, ss.

JUL 25 1984

(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Lloyd E Cooper  
(Address) 1702 Fleming Garden Pkwy, b

KAY B COOPER  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 6-8-85

SUBSCRIBED AND SWORN TO before me this 24<sup>th</sup> day of July, 1984

Kay B Cooper  
Notary Public

My Commission expires: June 3, 1985

OCT 15 1984

Form CP-4 1-84  
Revised 06-83