

15-203-00005 00-00
WELL PLUGGING RECORD


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WICHITA

County, Sec. 8 Twp. 20S Rge. 38W (E) (W)

Location as "NE/CNWxSWx" or footage from lines C SE NW
Lease Owner Shell Oil Company
Lease Name SHULI Well No. 1
Office Address 434 N. Oliver, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-7-60 19
Application for plugging filed 5-7-60 19
Application for plugging approved 5-7-60 19
Plugging commenced 5-7-60 19
Plugging completed 5-7-60 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Leiker, Victoria, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Shale	Surface Casing	-0-	249'	8-5/8"	249'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED HOLE:

Filled with heavy mud 5212' up to 600'. Pushed wood plug down to 600', cement plug with 50 sx. through drill pipe by Halliburton. Filled hole with mud up to 248'. Pushed down wood plug to 248', cemented plug with 25 sx. through drill pipe by Halliburton. Filled hole with heavy mud up to 40', wood plug, 15 sx. cement through drill pipe by Halliburton up to cellar Zero. Cemented 5 sx. in rat hole; 5 sx. in mouse hole.

Job Completed: 5-7-60 - 1:30 p.m.

STATE CORPORATION COMMISSION

MAY 10 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Co., Inc.
Address 208 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
C. T. HONAKER

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. T. Honaker C. T. HONAKER, DRLG. SUPT.

Box 232, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of MAY, 1960

George S. [Signature]

Notary Public.

My commission expires 10-17-63



15-203-00005-00-00

Shell Oil Comapny - - - - Operator
Sierra Petroleum Co., Inc. - Contractor

Elevation: 3448' D.F.
Total Depth: 5212'

SHUMI #1
C SE NW - Sec. 8-20S-38W
Wichita County, Kansas

Date Commenced: 4-14-60
Date Completed: 5-5-60

CASING:

8-5/8" Set a 249'

CEMENT:

with 175 sx. Cement

FORMATION	DEPTH
Sand	100'
Sand & Shale	250'
Shale	275'
Lime	330'
Shale	490'
Shale & Sand	1030'
Shale & Sand	1375'
Shale & Lime	1565'
Red Bed & Shale	1660'
Shale & Lime	1683'
Anhydrite & Shale	1900'
Red Bed & Shale	2140'
Red Bed & Sand	2345'
Shale	2510'
Red Bed & Anhydrite	2617'
Red Bed & Shale	2745'
Red Shale & Lime	2860'
Shale & Dolomite	2944'
Shale & Lime	3242'
Lime	3560'
Shale & Lime	3604'
Lime	3687'
Lime & Shale	3843'
Lime	4329'
Pokkes Lime	4345'
Lime	4531'
Lime & Shale	4561'
Lime	4658'
Shale & Lime	4705'
Lime	4777'
Lime & Shale	4822'
Lime	4901'
Lime & Shale	4929'
Lime & Sand	4954'
Sand & Shale	4975'
Shale & Lime	5112'
Lime	5212'

TOPS:	DEPTH
Heebner	3988'
Lans. K. C.	4036'
Marmaton	4525'
Cherakee	4648'
Morrow Sand	4924'
Top Mississippi	5112'

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

O. P. Henke

Subscribed and sworn to before me this 9th day of May, 1960.

Leroy Dietz
Notary Public

My commission expires: 10-17-63

MAY 10 1960
COUNTY OF RUSSELL
KANSAS