

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Wichita County, Sec. 22 Twp. 20 Rge. 36 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines NW, NW, NE
Lease Owner Rooney-Seigfried-Thomas
Lease Name B. F. Smith Well No. 1
Office Address Box 324--Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-1-54 1954
Application for plugging filed 12-30-53 1953
Application for plugging approved 12-30-53 1953
Plugging commenced 1-2-54 1954
Plugging completed 1-2-54 1954
Reason for abandonment of well or producing formation Dry Hole

NORTH

		X	

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5124 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing	Dry	4020		8 5/8"	282'	None
BKC	Marker	4423				
Cherokee	Dry	4841				
Mississippi	Dry	5084	5124			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled Hole with heavy mud to 280 feet and set plug with 1/3 sack of hulls on top of plug. Twenty (20) sacks of cement were then hand mixed and poured through the drill pipe on top of the plug.

Hole was then filled to 35 feet with heavy mud and plug was set with 1/3 sack of hulls on top of the plug. Ten (10) sacks of cement were then hand mixed and put on top of the plug.

01-07-1954

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SCHAFFER DRILLING COMPANY
Address BOX 350 PRATT, KANSAS

STATE OF KANSAS COUNTY OF PRATT, ss.
J. E. Selby (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. E. Selby
PRATT, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of January, 19 54

My commission expires February 25, 1956 Vilma Cantler Notary Public.

PLUGGING
FILE SEC 22 T 20 R 36W
BOOK 5 LINE 22

15-203-01001-00-00

DRILLER'S LOG
SMITH #1

ROONEY-SEIGFRIED-THOMAS
WICHITA COUNTY, KANSAS

0-40	Surface Clay
40-145	Sand
145-190	River Gravel
190-260	Shale & Shell
260-282	Blue Shale
282-350	Shale
350-800	Shale & Shell
800-1050	Sand & Shale
1050-1225	Shale & Shell
1225-1380	Sand & Shale
1380-1410	Shale & Red Rock
1410-1440	Shale
1440-1486	Anhydrite
1486-1760	Shale
1760-1900	Shale & Shell
1900-1950	Salt, Shale & Red Bed
1950-2045	Shale & Red Bed
2045-2265	Shale & Red Rock
2265-2525	Shale & Shells
2525-2655	Shale & Lime Shells
2655-3825	Shale & Lime
3825-4070	Lime
4070-4145	Shale & Lime
4145-4250	Lime
4250-4315	K. C. Lime
4315-4505	Lime
4505-4745	Shale & Lime
4745-4775	Brown Lime
4775-4797	Lime
4797-4930	Shale & Lime
4930-5077	Sand & Shale
5077-5124	Chert & Lime
5124	TOTAL DEPTH

I certify that the above drillers' log is true and correct as taken from the daily drilling reports of the Smith #1.

PLUGGING
 FILE SEC 22 T 20 R 364
 BOOK PAGE 5 LINE 32

J. E. Selby
 J. E. Selby
 SCHAFER DRILLING COMPANY

STATE OF KANSAS, COUNTY OF PRATT, SS:

Subscribed and sworn to before me this 31st day of December 1953.

My Commission expires Feb. 25, 1956. *Velda Coulter*
 Notary Public