

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-203-20,093-00-00

LEASE NAME Steven J. Graff

WELL NUMBER 1

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 11 TWP. 20S RGE. 36 ~~X&X&X~~(W)

COUNTY Wichita

Date Well Completed 6/14/90

Plugging Commenced 6/15/90

Plugging Completed _____

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Diversified Production Service

ADDRESS 8908 S. Yale #229, Tulsa, OK 74137

PHONE#(918) 493-1418 OPERATORS LICENSE NO. 3819

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/14/90 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom NTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				20"	44	None
				8 5/8	270	None

STATE CORPORATION COMMISSION
OIL & GAS
JUN 26 1990

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Filled hole w/heavy mud to 2250; 1st plug @ 2250 to 2050 w/50 sxs; 2nd plug @ 1200 to 880 w/80 sxs; 3rd plug at 600 to 400 w/50 sxs; 4th plug @ 300 to 100 w/50 sxs; 5th plug @ 40 to surface w/10 sxs; 15 sxs. in rathole. All cement 60/40 pozmix w/6% gel & 1/4# FloceI per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, #801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Diversified Production Service

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton, Agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, #801, Wichita, KS 67202

DEBORAH K. AMMERMAN
Notary Public - State of Kansas
My Appt. Expires 3-1-92

My Commission Expires: 3-1-92

Deborah K. Ammerman
Notary Public

15-~~203~~²⁰³-20093-00-00

ABERCROMBIE DRILLING, INC.

801 UNION CENTER
WICHITA, KANSAS 67202

Diversified Production Service
8908 S. Yale #229
Tulsa, OK 74137

STEVEN J. GRAFF #1
SW SE Sec. 11-20S-36W
Wichita County, KS

Contractor: Abercrombie Drilling, Inc.
Conductor: 20" set at 44' w/4 yds. Redimix
Surface: 8 5/8" set at 270' w/190 sxs.

DRILLERS WELL LOG

06-04-90	0 to 48	Sand and Shale
06-05-90	98 to 1300	Sand and Shale
06-06-90	1300 to 2187	Sand and Shale
06-07-90	2187 to 2243	Shale
	2243 to 2760	Shale and Lime
06-08-90	2760 to 3245	Shale
06-09-90	3245 to 3542	Shale
	3542 to 3720	Shale and Lime
06-10-90	3720 to 3920	Lime and Shale
	3920 to 4185	Shale and Lime
06-11-90	4185 to 4435	Shale and Lime
	4435 to 4515	Lime and Shale
06-12-90	4515 to 4529	Lime
	4529 to 4635	Lime and Shale
06-13-90	4635 to 4708	Lime
	4708 to 4925	Lime and Shale
06-14-90	4925 to 5080	Lime and Shale
	5080	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1990
06-26-1990
CONSERVATION DIVISION
Wichita, Kansas