

15-~~203~~-203-20023-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027

WELL PLUGGING RECORD

Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Wichita County, Sec 4 Twp 20S Rge (E) 36 (W)
Location as "NE/CNW/SW" or footage from lines C SW SW
Lease Owner Maurice L. Brown
Lease Name G. S. Smith "F" Well No. 1
Office Address 1500 Vickers/KSB&T Bldg., Wichita, 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 13, 1974
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced February 13, 1974
Plugging completed February 13, 1974
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (W. L. Nichols of Morland)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 5250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	285.80'	8-5/8"	285.80'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 900 Feet,
110 sax 50/50 Poz, 6% gel; Heavy Mud to
300 Feet, 30 sax Cement; Heavy Mud to
40 Feet, 10 sax Cement to Base of Cellar.
Job Completed @ 6:30 P.M.

RECEIVED
STATE CORPORATION COMMISSION
FEB 22 1974
02-22-1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Oil Well Cementing
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.
T. M. McCaul, Jr. of Sage Drlg. Co. (operator of owner or operator) of the above described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) T. M. McCaul, Jr.
500 Bitting Bldg., Wichita, Kansas (Address)

Subscribed and Sworn to before me this 18th day of February, 1974.

Louise K. Whitted
Louise K. Whitted Notary Public.

My Commission Expires November 26, 1974



15-071-203-20023-00-00

DRILLERS LOG

G. S. SMITH "F" NO. 1

CASING RECORD:	OPERATOR: Maurice L. Brown	DESCRIPTION:
8-5/8" set @ 285.80' w/225 sax cement	CONTRACTOR: Sage Drilling Co.	C SW SW Sec. 4-20S-36W Wichita Co., Kansas
TOTAL DEPTH: 5250'	COMMENCED: January 25, 1974	ELEVATION: 3237KB
	COMPLETED: February 13, 1974	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	195	
Sand	195	288	
Shale	288	1487	
Shale & Shells	1487	2222	
Shale	2222	2525	
Lime	2525	2698	
Shale	2698	2896	
Lime	2896	5250	

RECEIVED
STATE CORPORATION COMMISSION
FEB 22 1974
02-22-1974
CONSERVATION DIVISION
Wichita, Kansas
D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By T. M. McCaul, Jr.
T. M. McCaul, Jr.



Subscribed and sworn to before me this 18th day of February, 1974.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1974.