

15-171-20262-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Scott SEC. 35 TWP. 17S RGE. 33 X/W
 Location as in quarters or footage from lines:
2640' FNL & 400' FWL

Lease Owner Anadarko Production Company
 Lease Name Frick "A" Well No. 1
 Office Address Box 351, Liberal, Kansas 67901
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 11/15/83
 Application for plugging filed 11/14/83 Verbal
 Plugging commenced 11/14/83
 Plugging completed 11/15/83
 Reason for abandonment of well or producing formation Dry hole.

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes (CL)

Name of Conservation Agent who supervised plugging of this well Paul Luthi

Producing formation _____ Depth to top _____ bottom _____ T.D. 4950

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	1374	0'	1374'	8-5/8	1374	0

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. All cement plugs 60-40 Pozmix + 2% Gel, 3% CaCl₂,
 spotted 50 sxs cement 2280-2030', 60 sxs cmt 1440-1165', 25 sxs cement 730-605', pushed
 wooden plug to 50', cement with 10 sxs cement to ground level, 10 sxs cement in rathole,
 circulate thru plugging operations.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company
200 Douglas Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Seward, ss.
Paul Campbell (employee of owner) or ~~(owner or operator)~~ of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell
Box 351, Liberal, Kansas 67901
 (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 19 83

RECEIVED
 STATE CORPORATION COMMISSION

My Commission expires: 12-20-83
 CONSERVATION DIVISION
 Wichita, Kansas

ELIZABETH J. HOOPER
 Seward County, Kansas
 My App. Expires 7-26-87

Elizabeth J. Hooper
 Notary Public.