

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171,20,436-000

LEASE NAME Hermes

WELL NUMBER #1

4950 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 34 TWP. 17 SRGE. 31 ~~XXXX~~ (W)

COUNTY Scott

Date Well Completed 9-20-91

Plugging Commenced 9-20-91

Plugging Completed 9-20-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anderson Energy, Inc.

ADDRESS 200 E. First St. - Suite 414

Wichita, KS 67202

PHONE#(316) 265-7929 OPERATORS LICENSE NO. 6486

6484

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 20, 1991 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4575'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	330	None

SEP 27 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spotted 50 sacks cement at 2300' thru drill pipe. Spotted 10 sacks cement at
Spotted 80 sacks cement at 1475' thru drill pipe. 40' thru drill pipe.
Spotted 50 sacks cement at 725' thru drill pipe. Spotted 15 sacks cement
Spotted 50 sacks cement at 360' thru drill pipe. in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 48848, Wichita, KS 67201-8848

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anderson Energy, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine

(Address) P. O. Box 48848
Wichita, KS 67201-8848

SUBSCRIBED AND SWORN TO before me this 26th day of September, 19 91


My Commission Expires:

Carolyn J. Tjaden
CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. Sept. 5, 1992

Notary Public

15-17-20436-00-00

RECEIVED
STATE OF KANSAS
CONSERVATION COMMISSION



SEP 27 1991

CONSERVATION DIVISION
Wichita, Kansas

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Anderson Energy, Inc., 200 E. First St. - Suite 414
Wichita, KS 67202
CONTRACTOR: White & Ellis Drilling, Inc. 401 E. Douglas - Suite 500
Wichita, Kansas 67202

Lease Name Hermes Well No. 1
Sec. 34 T. 17S R. 31W Spot NW NE NW
County Scott State Kansas Elev. _____

Casing Record:

Surface: 8 5/8" @ 330' with 200 sx.
Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4575'

Drilling Commenced 9-11-91 Drilling Completed 9-19-91

Formation	From	To	Tops
Cellar	0	5	Anhydrite 2268
Sand & Shales	5	810	Topeka 3760
Shales & Sand	810	1685	Lansing 3935
Sand	1440	1475	Lansing-KC 3966
Shales	1475	1864	Kansas City 4020
Sand	1864	2010	Stark 4184
Shales	2010	2960	Marmaton 4335
Shales & Lime	2960	3350	Johnson/
Shales	3350	3550	Mississippi 4485
Shales & Lime	3550	3760	
Lime & Shale	3760	4485	
Lime, Sand & Shale	4485	4575	