

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-20,409-00-00

LEASE NAME Delmar Huck

WELL NUMBER 1

3300 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 32 TWP. 17S RGE. 31 (XXX)(W)

COUNTY Scott

Date Well Completed 06-04-90

Plugging Commenced 06-05-90

Plugging Completed 06-05-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 150 N. Main, #801, Wichita, KS 67202

PHONE#(316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 06-05-90 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	<u>26 JUN 26 1990</u>			<u>8 5/8</u>	<u>262.87</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Filled hole w/heavy mud to 2310', 1st plug 2310' to 2110' w/50 sxs; 2nd plug from 1450' to 1130' w/80 sxs; 3rd plug from 725' to 625' w/25 sxs; 4th plug from 300' to 100' w/50 sxs; 5th plug from 40' to surface w/10 sxs; 15 sxs. in rathole. All cement 60/40 pozmix w/6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, #801, Wichita, KS 67202


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main #801, Wichita, KS



SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 90

Deborah K. Ammerman
Notary Public

My Commission Expires: 3-1-92

15-171-20409-00-00

ABERCROMBIE DRILLING, INC.

801 UNION CENTER
WICHITA, KANSAS 67202

A. L. Abercrombie, Inc.
150 N. Main, #801
Wichita, KS 67202

DELMAR HUCK #1
W/2 SE NE Sec. 32-17S-31W
Scott County, KS

Contractor: Abercrombie Drilling, Inc.
Surface: 8 5/8 set @ 262.87 w/150 sxs.

DRILLERS WELL LOG

05-26-90	0 to 267	Clay, Sand and Shale
05-27-90	267 to 525	Shale and Sand
	525 to 1350	Sand and Shale
	1350 to 1790	Shale and Sand
05-28-90	1790 to 2284	Shale and Sand
	2284 to 2303	Anhydrite
	2303 to 2600	Shale and Sand
	2600 to 2880	Shale and Lime
05-29-90	2880 to 3305	Shale and Lime
	3305 to 3387	Lime and Shale
05-30-90	3387 to 3780	Shale and Lime
	3780 to 3940	Lime and Shale
05-31-90	3940 to 3978	Shale and Lime
	3978 to 4035	Lime
06-01-90	4035 to 4160	Shale and Lime
	4160 to 4201	Lime and Shale
06-02-90	4201 to 4231	Shale and Lime
	4231 to 4310	Lime and Shale
06-03-90	4310 to 4470	Shale and Lime
	4470 to 4550	Lime and Chert
06-04-90	4550 to 4575	Lime and Shale
	4575 to 4625	Lime
	4625	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1990.

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1990.

CONSERVATION DIVISION
Wichita, Kansas