


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Scott County, Sec. 30 Twp. 17 Rge. 31 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW
Lease Owner Bell Oil & Gas Co.
Lease Name Durrant Well No. 2
Office Address P. O. Box 2007, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 25 19 61
Application for plugging filed May 25 19 61
Application for plugging approved May 25 19 61
Plugging commenced May 25 19 61
Plugging completed May 25 19 61
Reason for abandonment of well or producing formation no oil &/or gas found
in commercial quantities
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4700 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	268	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 560', set Plug #1 at 560' w/20 sx. cement.
Filled hole with extra heavy rotary mud from Plug #1 to 260'. Set Plug #2 at 260' w/20 sacks cement.
Filled hole with extra heavy rotary mud from Plug #2 to 40', set Plug #3 at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 31 1961

CONSERVATION DIVISION
Wichita, Kansas

05-31-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.
Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.R. McNicol
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of May, 19 61

My commission expires Sept. 30, 1963

Darlene May
Notary Public.

15-171-19004-00-00

ROTARY DRILLING LOG

OPERATOR: Bell Oil & Gas Company
No. 2 Durrant
NW NW Sec. 30-17S-31W,
Scott County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
COMM: 5-10-61
COMP: 5-25-61

Remarks: Set 8-5/8" casing at
268' cemented with 225
sacks cement

Formations:

Shale	50'
Sand	160'
Shale & Shells	255'
Shale	1543'
Shale & Shells	1920'
Shale	2317'
Shale & Red Bed	2508'
Shale & Shells	2710'
Shale & Lime	2818'
Lime & Shale	2946'
Lime	3140'
Lime & Shale	3686'
Lime	3919'
Lime & Shale	4015'
Lime	4147'
Lime & Shale	4242'
Lime	4462'
Lime & Shale	4509'
Lime	4700'
Rotary Total Depth(D&A)	4700'

RECEIVED
STATE CONSERVATION COMMISSION
MAY 31 1961
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and
correct to the best of our knowledge
and belief.

CAPITT DRILLING, INC.

R. R. McNicol

R. R. McNicol