

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-171-20,470-00-00

LEASE NAME Brookover

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

2310 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 30 TWP. 17S RGE. 31 (E/W of (L/W))

COUNTY Scott

LEASE OPERATOR Wabash Energy Corporation

ADDRESS P. O. Box 595, Lawrenceville, IL 62439

PHONE# (618) -943-3365 OPERATORS LICENSE NO. 31251

Date Well Completed 7/29/94

Character of Well D&A

Plugging Commenced 7/29/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/29/94

The plugging proposal was approved on 7-29-94 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4695'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	240'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4695'-2330' 50 sks cement @ 270'  
50 sks cement @ 2330' 10 sks cement @ 40'  
50 sks cement @ 1740' 10 sks in mousehole  
50 sks cement @ 820' 15 sks in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Wabash Energy Corporation

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kyle B. Branum  
(Address) Box 506, Russell, KS 67665-0506

RECEIVED  
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 1st day of August AUG 9 1994

GLEND A R. TIFFIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 2-6-94

Glenda R. Tiffin  
Glenda R. Tiffin, Notary Public  
CONSERVATION DIVISION  
WICHITA, KANSAS

15-171-20470-00-00

EMPHASIS OIL OPERATIONS  
A Division of N-B Company, Inc.  
P. O. BOX 506  
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Wabash Energy Corporation  
P. O. Box 595  
Lawrenceville, IL 62439

CONTRACTOR: Emphasis Oil Operations  
Box 506  
Russell, KS 67665

LEASE: Brookover

WELL #2

LOCATION: NE NE SW  
Section 30-17S-31W  
Scott County, Kansas

LOGGERS TOTAL DEPTH: 4695'

ROTARY TOTAL DEPTH: 4695'

COMMENCED: 7/21/94

CASING: 8-5/8" @ 240' w/150 sks cement

ELEVATION: 2960' K.B.

COMPLETED: 7/29/94

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Sand & Shale	140'	Lime & Shale	3911'
Anhydrite	2308'	Lime	4190'
Shale	2330'	Mississippi	4638'
Shale & Lime	3755'	R.T.D.	4695'


STATE OF KANSAS )  
                          ) ss  
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

  
Kyle B. Branum

Subscribed and sworn to before me on August 1, 1994.

My commission expires: February 6, 1996.



  
Glenda R. Tiffin, Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 09 1994  
CONSERVATION DIVISION  
WICHITA, KANSAS