

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-171-20,397 0000

LEASE NAME Huck "B"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

1980 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 29 TWP. 17S RGE. 31 ~~W~~ (W)

COUNTY Scott

Date Well Completed 11-10-89

Plugging Commenced 11-10-89

Plugging Completed 11-10-89

LEASE OPERATOR A. L. Abercrombie, Inc.

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67101

PHONE# (316) 262-1841 OPERATORS LICENSE NO. 5393

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-10-89 (date)

by State Plugger, Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4630'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	247.37'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circulate heavy mud in hole. 1st plug from 2320' to 2120' w/50 sx. 2nd plug from 1300' to 980' w/80 sx. 3rd plug from 270' to 110' w/40 sx. 4th plug from 40' with wiper plug to surface w/10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A. L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. DEC 12 - 05 - 89  
5 1989

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well in Kansas filed that the same are true and correct, so help me God.


(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801

Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 4th day of December, 1989

Sharan J. Branstetter  
Sharan J. Branstetter Notary Public  
May 18, 1993



\*DST #5 (4458'-4554') Ft. Scott and Johnson Zone

30-45-30-45, Rec. 15' oil sptd mud

IFP 31-31 ISIP 202

FFP 42-42 FSIP 127

\*DST #6 (4115'-4140') H zone Lansing

(Straddle packers)

30-45-60-45, Rec. 217' oil sptd wtry mud and

992' wtr.

IFP 85-255 ISIP 949

FFP 319-541 FSIP 939