

RECEIVED

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

DEC 05 2001

KCC WICHITA WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-203-20031-00-60 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. *69*

WELL OPERATOR Kaiser-Francis Oil Company KCC LICENSE # 6568 *102-*
(owner/company name) (operator's)

ADDRESS P. O. Box 21468 CITY Tulsa

STATE OK ZIP CODE 74121-1468 CONTACT PHONE # (918) 491-4314

LEASE Caldwell WELL# C 1 SEC. 34 T. 20S R. 38 (~~West~~/West)

- - SW - SW SPOT LOCATION/QQQQ COUNTY Wichita

550 FEET (in exact footage) FROM S/ (circle one) LINE OF SECTION (NOT Lease Line)

765 FEET (in exact footage) FROM /W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 345 CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 4878 CEMENTED WITH 150 SACKS

Casing has been squeezed twice for csg. leaks: 2876-2902 (100 sxs) 2573-2619 (100sxs)
LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4788-4794; 4820-4830; 4836-4842

ELEVATION 3408 T.D. 4878 PBD 4849 ANHYDRITE DEPTH Unk.
(G.L./) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 4650'. Locate casing free-point. Cut off csg.

Spot cmt plugs as directed by KCC District Office.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? On old form

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

John Glenn, Supt. PHONE# (620) 564-3214

ADDRESS 513 E. 3rd City/State Ellinwood, KS

PLUGGING CONTRACTOR Allied Cement Company KCC LICENSE # 99996
(company name) (contractor's)

ADDRESS 1612 N. Clay, Medicine Lodge, KS PHONE# ()

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon approval *well plugged*

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11/30/01 AUTHORIZED OPERATOR/AGENT: C. Jan Valkenburg
(signature)
Charlotte Van Valkenburg

RECEIVED

DEC 0 5 2001

KCC WICHITA
DRILLERS LOG

CALDWELL NO. 1

CASING RECORD:	OPERATOR: Cameron Funk	DESCRIPTION:
8-5/8" set @ 339.50' w/250 sax cement	CONTRACTOR: Sage Drilling Co.	Ap C SW SW Sec. 34-20S-38W Wichita Co., Kans.
TOTAL DEPTH: 4880'	COMMENCED: February 3, 1976	ELEVATION: 3413KB
	COMPLETED: February 15, 1976	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	345	
Shale & Sand	345	1260	
Shale	1260	1630	
Sand & Shale	1630	2350	
Lime & Shale	2350	2870	
Shale & Lime	2870	3075	
Lime & Shale	3075	3243	
Shale & Lime	3243	3350	
Lime & Shale	3350	3635	
Shale & Lime	3635	3785	
Lime & Shale	3785	4100	
Shale & Lime	4100	4215	
Lime & Shale	4215	4445	
Shale & Lime	4445	4503	
Lime & Shale	4503	4530	
Lime	4530	4600	
Lime & Shale	4600	4650	
Shale & Lime	4650	4735	
Lime & Shale	4735	4820	
Lime	4820	4880	5 1/2" set @ 4878' w/150 sax cement


I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

T. M. McCaul, Jr.

By T. M. McCaul, Jr.

Subscribed and sworn to before me this 26th day of February, 1976.



Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1978.