

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-203-20,111-00-09 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR WOOLSEY PETROLEUM CORPORATION KCC LICENSE # 5506
(owner/company name) (operator's)

ADDRESS 107 N. MARKET, SUITE 600 CITY WICHITA

STATE KANSAS ZIP CODE 67202 CONTACT PHONE # (316) 267-4379

LEASE BERNICE SMITH WELL# 1 SEC. 3 T. 20S R. 36 (East/West)

C - N/2 - NW - SW SPCT LOCATION/QQQQ COUNTY WICHITA

2310' FSL FEET (in exact footage) FROM S/W (circle one) LINE OF SECTION (NOT Lease Line)

660' FWL FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 207.98 CEMENTED WITH 60-40 posmix / 160 sx SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: n/a

ELEVATION 3223' / 3228' T.D. 5800' PETD _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 3000' w/100 sx; 2nd plug @ 2262' w/50 sx; 3rd plug @ 1250' w/80 sx; 4th plug @ 450' w/50 sx; 5th plug @ 240' w/50 sx; 6th plug @ 40' w/10 sx; rathole 15 sx; Total 345 sx 60-40 posmix 6% gel 1/4# Floseal/sk.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? KANSAS CORPORATION COMMISSION

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. sec. AND THE RULES AND REGULATIONS OF THE KANSAS CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Fisher WICHITA, KS PHONE# () _____

ADDRESS P.O. Box 673 City/State Scott City, KS 67871-0673

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684
(company name) (contractor's)

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (if known?) Complete @ 12:18 a.m. 6-8-94

PAYMENT OF THE PLUGGING FEE (K.S.A. 52-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 08/05/94 AUTHORIZED OPERATOR/AGENT: I. Wayne Woolsey
(signature)

I. Wayne Woolsey, President