

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-171-20,409-000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR A. L. Abercrombie, Inc. OPERATOR'S LICENSE NO. 5393

ADDRESS 150 N. Main, #801, Wichita, KS 67202 PHONE # (316) 262-1841

LEASE (FARM) Delmar Huck WELL NO. 1 WELL LOCATION W/2 SE NE COUNTY Scott

SEC. 32 TWP. 17S RGE. 31 (~~E~~~~X~~~~E~~~~W~~) TOTAL DEPTH 4625 PLUG BACK TO _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO: CEIVED

SURFACE CASING SIZE 8 5/8" SET AT 262.87 CEMENTED WITH 150 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING 1st plug @ 2310' w/50 sxs; 2nd plug @ 1450' w/80 sxs;

3rd plug @ 725' w/50 sxs; 4th plug @ 300' w/50 sxs; 5th plug @ 40' w/10 sxs; 15 sxs. in

rathole. All cement 60/40 pozmix 6% gel 1/4# Flocel per sx.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 7:00 a.m. 06-05-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Anthony Martin

ADDRESS 533 N. Main, Wakeeney, KS 67672 PHONE # (913) 743-5443

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, #801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton

(Operator or Agent)

DATE: 6-22-90