

15-203-20020-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Salsxy Oil Company,
Complete Address 918 Lamar Street, Wichita Falls, Texas. 76301
Lease Name Lewis Well No. 1
Location CSE-SE Sec. 22 Twp. 16 Rge. (E) (W) 37
County Wichita Total Depth 3258'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Dowell Division-Dowell Chemical Co.,
Address Box #525, Ulysses, Kansas. License No.
Operation Completed: Hour 7:45 PM Day 17 Month 3 Year 1974

The above well was plugged as follows:

309'--8 5/8" Surface casing, cement circulated with 200 Sx.
3258'--4 1/2" casing cemented on bottom with 160 Sx. Top perforations from 2867' to 2878'.
Set Wellex Wire Line Bridge Plug @ 2700' and 10' cement on top with dump bailer. Shot off 4 1/2" casing @ 1000', pulled 1 joint and displaced 200 Sx. cement thru 4 1/2" to base of surface. Pulled 4 1/2", set bridge & 10' cement to bottom of cellar. Cut off surface casing 3' below ground level and welded on steel cap.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dechels
Well Plugging Supervisor

INVOICED

DATE 4/2/74

INV. NO. 8844-U