

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 23 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Galaxy Oil Company,

Complete Address 918 Lamar Street, Wichita Falls, Texas.

Lease Name Smades Well No. 1

Location CSE-SE Sec. 15 Twp. 17 Rge. (E) (W) 36

County Wichita Total Depth 3050'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Ks. License No.     

Operation Completed: Hour 11:30 PM Day 19 Month 3 Year 1973

The above well was plugged as follows:

307'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 110 Cu. Ft. cement  
thru DP from 1125' to 800'. Pulled DP to 315' and displaced 30 Cu. Ft. cement thru  
DP from 315' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 3-23-73

INV. NO. 7163-U