

15-203-00015-00-00

R

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1959

CONSERVATION DIVISION
Wichita, Kansas

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 62-42 County: Wichita
Location: C. N.W. N.W. Sec. 16 Twp. 17 Rge. 37 (E) (W)
Name of Field: Nelson Total Depth: 6000

I have this date completed supervision of plugging of:

Lease Name: Nelson Well No. 1

Operator's Full Name: Panhandle Eastern

Complete Address: Box 979 - Liberal Kansas

Plugging Contractor: Daro Lease & Mill Sewer

Address: 1700 So Main Borger Texas License No. 138

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Was any delay in plugging operations caused by Conservation Division Agent? Yes No X

If yes how long? Reason:

Operation Completed: Hour 8pm Day 27 Month Aug Year 1959

The above well was plugged as follows:

D.D. 6000 - Bored back to 4617' - 8 7/8 set at 547 with 275 sac 4 1/2" set at 4607
Perf. 4528 to 4532 - Sand to 4518 and 20 sac cement pumped by
Hubbenton thru tubing. Shot pipe at 2835 and pulled sand to
700' and circulated. Rble with mud, pulled pipe up to 560' and
pumped 20 sac cement, pulled 4 1/2" up to 210' and pumped 20 sac
cement, pulled 4 1/2" out of hole thru rock bridge and 10 sac
cement. Cementing to base of cellar.

Signed: Robert O. Licker
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

INVOICED

DATE 12/2/59

INV. NO. 146-W