

15-203-20016-00-00



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Galaxy Oil Company,
Complete Address 918 Lamar Street, Wichita Falls, Texas.
Lease Name Flatland Farms Well No. 1
Location C NE NE Sec. 26 Twp. 17 Rge. 18 (E) 38 (W)
County Wichita Total Depth 2910'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Dowell Division-Dowell Chemical Co.,
Address Box #525, Ulysses, Kansas. License No.
Operation Completed: Hour 8:15 PM Day 16 Month 3 Year 1974

The above well was plugged as follows:

322'--10 3/4" Surface casing, cement circulated.
2818'--7" OD casing cemented on bottom with 125 Sx. Open hole completion.
Set Welex wire line bridge plug @ 2285' and 6' cement on top with dump bailer.
Shot off 7" casing @ 985', pulled 1 joint and displaced 250 Sx. cement thru 7" to
base of surface casing. Pulled 7" casing, set bridge and 10' cement to bottom of
cellar. Cut off 10 3/4" casing 3' below ground level and welded on steel cap.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. D. [Signature]
Well Plugging Supervisor

INVOICED

DATE 4/2/74
INV. NO. 8842-W