

15-203-20012-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 1 - 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Jerry D. Fouts or Cactus Operating Company,
Complete Address 918 Lamar Street, Wichita, Falls, Texas.
Lease Name Kessler Well No. 1
Location Appr:-C of Sec. 18 Twp. 18 Rge. (E) (W) 35
County Wichita Total Depth 2835'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Dowell Division--Dowell Chemical Company,
Address P. O. Box # 525, Ulysses, Kansas. License No.
Operation Completed: Hour 7:30 PM Day 19 Month 3 Year 1974

The above well was plugged as follows:

350'--10 3/4" Surface casing, cement circulated.
2775'--7" OD casing cemented on bottom with 125 Sx. Open hole completion.
Set 7" Welex wire line bridge plug @ 2400' and 6' cement on top with dump bailer.
Shot off 7" casing @ 850', pulled 1 joint and displaced 200 Sx. cement thru 7" casing
to base of surface pipe. Pulled 7", set bridge and 10' cement to bottom of cellar.
Cut off Surface casing 3' below ground level and welded on steel cap.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 4/2/74

INV. NO. 8839-W