

*[Handwritten mark]*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 11 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Davidor & Davidor, Incorporated,

Complete Address 4515 North Santa Fe, Oklahoma City, Oklahoma.

Lease Name Everett Caldwell Well No. B-1

Location NW-SW Sec. 34 Twp. 20 Rge. (E) (W) 38

County Wichita Total Depth 4915'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 4:30 AM Day 8 Month 4 Year 1968

The above well was plugged as follows:

320'--8 5/8" Surface pipe, cement circulated with 225 Sx.  
Top of Dakota Section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 100 Sx. cement thru  
DP from 1025' to 700'. Pulled DP to 330' and displaced 25 Sx. cement thru DP from  
330' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *[Signature]*  
Well Plugging Supervisor

INDEXED

DATE 4/11/68  
INV. NO. 7569-4