

KANSAS 15-203-20005-0000

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Davidor & Davidor, Incorporated,

Complete Address 4515 North Santa Fe, Oklahoma City, Oklahoma.

Lease Name A. J. Rupp Well No. 1-21

Location SW-SE Sec. 21 Twp. 20 Rge. (E) (W) 38

County Wichita Total Depth 5209'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Earl F. Wakefield.

Address 515 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour # 3:45AM Day 14 Month 1 Year 1968

The above well was plugged as follows:

330'--8 5/8" Surface pipe, cement circulated with 250 Sx.
Dakota section from 735' to 950'.

Circulated hole with heavy mud. Pulled DP to 100' and displaced 100 Sx. cement thru
DP from 1000' to 675'. Pulled DP to 360' and displaced 25 Sx. cement thru DP from
360' to 285'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1968

I hereby certify that the CONSERVATION DIVISION was plugged as herein stated.
Wichita, Kansas

Signed: H. L. Nichols
Well Plugging Supervisor

1/17/68
DIV. NO. 7108-W