

15-203-00001-00-00

KANSAS  
STATE CORPORATION COMMISSION

FEB 1962

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

CONSERVATION DIVISION  
Wichita, Kansas

02-09-1962

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Wichita

Location; SW SW Sec. 33 Twp. 20 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 36

Name of Field: \_\_\_\_\_ Total Depth: 5242

I have this date completed supervision of plugging of:

Lease Name: Sonderegger Well No. 1

Operator's Full Name: Anadarko Production Co

Complete Address: Box 351 Liberal, Kansas

Plugging Contractor Knight Casing Pulling

Address: Chase, Kansas License No. 436

Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No X

If Yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 8PM Day 2 Month 2 Year 62

The above well was plugged as follows:

13" 288' circulated with cement - 8" 2246' with 200 sax cement - ~~4 1/2"~~ hole  
mudded back to 3300', set 25 sax cement at 3300' - set 4 1/2" at 2985'  
with 125 sax cement - perf 2739 - PB 2733' - filled with sand to 2710'  
set 3 sax cement with dump bailer - pulled 2500' 4 1/2" 7 1780' 8 5/8"  
filled hole with heavy chunk mud to 270', set rock and 20 sax cement - heavy  
chunk mud to 25', set rock bridge and 10 sax cement to bottom cellar.

Signed: Edson Perry  
Conservation Division Agent

Reviewed: Harold Hollis  
Field Supervisor

Remarks:

INDEXED

2/12/62

4530-u