

15-203-20023-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1974
02-19-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Maurice L. Brown Trust & I. W. Woolsey,

Complete Address 1500 Vickers KSB&P Building, Wichita, Kansas.

Lease Name G. S. Smith Well No. F-1

Location CSW-SW Sec. 4 Twp. 20 Rge. (E) (W) 36

County Wichita Total Depth 5250'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Ks. License No.

Operation Completed: Hour 4:45 PM Day 13 Month 2 Year 1974

The above well was plugged as follows:

285'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 675'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 110 Cu. Ft. cement
thru DP from 900' to 575'. Pulled DP to 300' and displaced 30 Cu. Ft. cement thru
DP from 300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Dinkel
Well Plugging Supervisor

INVOICED

DATE 2/20/74

INV. NO. 8609-W