

15-171-80022-00-00

74

KANSAS STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO: Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

9-6-61

File No. _____ County: Scott
Location: CSE NW Sec. 30 Twp. 17 Rge. _____ (E) _____ (W) 31
Name of Field: _____ Total Depth: 4725

I have this date completed supervision of plugging of:

Lease Name: Durrant Well No. 1

Operator's Full Name: Bell Oil & Gas

Complete Address: Box 2007 Tulsa, Okla

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kansas License No. 399

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 29 Month 8 Year 61

The above well was plugged as follows:

8 5/8" 225' circulated with cement - 4 1/2" 4724' with 100 sax cement - perforated 4650' .

Filled with sand to 4630', set 4 sax cement with dump bailer, pulled 3800' 4 1/2" - filled hole with heavy chunk mud to 225', set rock and 25 sax cement, heavy mud to 40', set rock bridge and 10 sax cement to bottom cellar.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 9/8/61
INV. NO. 3901-W