

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Incorporated,

Complete Address Box #18407, Wichita, Kansas.

Lease Name Huck Well No. C-1

Location NE-NW Sec. 29 Twp. 17 Rge. (E) (W) 31

County Scott Total Depth 4635'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 220 W. Douglas, Wichita, Kansas. License No.

Operation Completed: Hour 5:30 PM Day 13 Month 5 Year 1974

The above well was plugged as follows:

645'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 110 Cu. Ft. cement
thru DP from 1225' to 900'. Pulled DP to 650' and displaced 30 Cu. Ft. cement thru
DP from 650' to 575'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/15/74
INV. NO. 9129-W