

15-171-20064-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 31 1974

CONSERVATION DIVISION
Wichita, Kansas
05-31-1974

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling Company, Incorporated.

Complete Address P. O. Box #18407, Wichita, Kansas.

Lease Name Huck Well No. A-1

Location GSW-SW Sec. 36 Twp. 17 Rge. (E) (W) 32

County Scott Total Depth 4645'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated.

Address 220 W. Douglas, Wichita, Kansas. License No.

Operation Completed: Hour 7:30 AM Day 29 Month 5 Year 1974

The above well was plugged as follows:

605'--8 5/8" Surface casing, cement circulated with 320 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 620' and displaced 30 Cu. Ft. cement thru
DP from 620' to 550'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

NOTICED
DATE 6/5/74
INV. NO. 9250-W