

15-171-00074-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1963
08-05-1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Morrison Producing Company,

Complete Address: 400 No. Main, Box #712, Eldorado, Kansas.

Lease Name Huck Well No. 1

Location CSE-SE Sec. 35 Twp. 17 Rge. (E) (W) 32

County Scott Total Depth 4790'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Heliar Drilling Company, Inc.,

Address: 1014 Union Center, Wichita, Kans. License No.

Operation Completed: Hour 3:00PM Day 2 Month 8 Year 1963

The Above well was plugged as follows:

320'--8 5/8" Surface pipe, cement circulated with 275 Sx.
Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx cement
thru DP. Heavy mud to 300', set plug with 1/4 sack hulls and displaced 20 Sx
cement thru D^r. Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Nichols
Well Plugging Supervisor

DATE 8/5/63
INV. NO. 7518-W