

15-171-20072-00-00



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

NOV 27 1974  
11-27-1974  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Krupp Well No. 1

Location CNW-SW Sec. 25 Twp. 17 Rge. (E) (W) 32

County Scott Total Depth 4648'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita, Plaza, Wichita, Ks. License No.     

Operation Completed: Hour 12:15 AM Day 22 Month 11 Year 1974

The above well was plugged as follows:

315'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement  
thru DP from 1275' to 950'. Pulled DP to 315' and displaced 30 Cu. Ft. cement thru  
DP from 315' to 240'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 12/2/74  
INV. NO. 279-W