

15-171-20073-00-00



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1974  
12-23-1974  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Omar Oil Company

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Stegman Well No. 1

Location C NW SE Sec. 24 Twp. 17 Rge. (E) (W) 32

County Scott Total Depth 4050'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 5:15 P Day 20 Month 12 Year 1974

The above well was plugged as follows:

RTD 4050' 8 5/8 csg set at 362' cwc Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cem plug at 975' thru drill pipe.

Heavy mud to 240' set 20 sk cem plug thru drill pipe. Heavy mud to 40' set

solid bridge & 10 sx cem to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lea P. Masey  
Well Plugging Supervisor

DATE 12/24/74

INV. NO. 532-W