

P

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JAN 17 1977  
01-17-1977

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-171-20108-00-00 (of this well)

Operator's Full Name Car Ben Inc.  
Complete Address 645 R.H. Garry Bldg 300 W. Douglas, Wichita, KS  
Lease Name Sprier Well No. 1-20-  
Location C. SW. Sec. 20 Twp. 17 Rge. 32 (E) (W) 1  
County Scott Total Depth 2925  
Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling  
Address Sublett, KS License No. 706

Operation Completed: Hour 3:00 PM Day 12 Month Jan Year 1977

The above well was plugged as follows:

SP, 8 5/8" - 356' c.w.c. - 4 1/2" oil string, set @ 2924'  
w/175 sx, 5 1/2" Perm. Recovered 2140' of 4 1/2" casing.  
Perf @ 2822-2829' Pumped down 4 1/2" to Plug Bottom  
1 sx Hulls, + 10 sx. com. com. to 2675'. Pumped  
Down 8 5/8" 25 sx. com. com. from 1000' to 920', 25 sx  
com. com. 350' to 270' + 10 sx. com. com. 40' to 0'.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-17-77  
INV. NO. 4494-W

Signed Gilbert Batthauer  
Well Plugging Supervisor