

15-171-30067-00-00

Form CP-3  
Rev. 6-26-62

16  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 1965

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Saturn Oil and Gas Company,

Complete Address: Box # 176, Cheyenne, Wyoming.

Lease Name Smith Well No. 2-35

Location CNE Sec. 35 Twp. 19 Rge. (E) (W) 33

County Scott Total Depth 2668

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Sargents Casing Pulling Service,

Address: Box #506, Liberal, Kansas License No. 511

Operation Completed: Hour 5:30PM Day 18 Month 5 Year 1965

The Above well was plugged as follows:

348'--8 5/8" Surface pipe, cement circulated with 250 Sx. 2668'--4 1/2"  
Production casing cemented with 100 Sx. Top of cement @ 2208'. Top per-  
forations @ 2526' to 2536.

Spotted 10 sacks cement in 4 1/2" with top @ 2410'. Pulled 4 1/2" to 600' and  
circulated heavy gel mud. (used 9 sacks gel). Pulled 4 1/2" to 540' and dis-  
placed 20 Sx. cement thru 4 1/2". Pulled 4 1/2" to 275' and displaced 20 Sx.  
cement thru 4 1/2". Pulled 4 1/2", set bridge @ 35' and 10 Sx. cement to  
bottom of cellar. (Recovered 2200' 4 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 5/24/65

INV. NO. 1208-W