

15-171-20020-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Yucca Petroleum Company,
Complete Address: Box #2585, Amarillo, Texas.
Lease Name Irma Well No. X-1 (TWIN)
Location 10'E of 150' N of CSE-SE Sec. 27 Twp. 19 Rge. (E) (W) 33
County Scott Total Depth 4751'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated: _____
Plugging Contractor: Leben Drilling, Incorporated,
Address: Box #486, Great Bend, Kansas. License No. _____
Operation Completed: Hour 2:45 AM Day 28 Month 4 Year 1969

The Above well was plugged as follows:

374'--8 5/8" Surface casing, cement circulated with 250 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 4500' and displaced 50 Sx. cement.

Pulled DP to 925' and displaced 100 Sx. cement thru DP from 925' to 600'. Pulled DP
to 400' and displaced 20 Sx. cement thru DP from 400' to 340'. Pulled DP, set bridge
@ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

5/2/69

INV. NO.

9699-W

Signed:

A. L. Dichel

Well Plugging Supervisor