

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 34320 Name: Lasso Energy LLC Address 1: P.O. Box 465 City: Chase State: KS Zip: 67524 Contact Person: Bruce Kelso Phone: (918) 633-9655 Type of Well: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Depth to Top: Bottom: T.D.

API No. 15 - 007227240000 Spot Description: C-NE NW NW Sec. 34 Twp. 38 S. R. 15 East West 330 Feet from North South Line of Section 990 Feet from East West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Barber Lease Name: Packard 4-23 Well #: 1-24 Date Well Completed: The plugging proposal was approved on: Steve Peifer (KCC District Agent's Name) Plugging Commenced: 12/13/11 Plugging Completed: 12/15/11

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows show casing sizes of 8-5/8" and 4-1/2" with setting depths of 217' and 4574' respectively.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Check hole, TD @ 4378', sanded bottom to 1450'. Pulled 25" stretch. Cut pipe at 3200'. Pumped 50sx at 2780'. Pulled up to 620', pumped 10sx gel 50sx cement. Pulled up to 250', pumped 50sx 60/40poz 4% gel. Pulled to 40', circulated to surface with 40sx cement. Plugging Complete.

Plugging Contractor License #: 31529 Name: Mike's Testing and Salvage, Inc. Address 1: PO Box 467 Address 2: City: Chase State: KS Zip: 67524 Phone: (620) 938-2943 Name of Party Responsible for Plugging Fees: Lasso Energy, LLC State of Kansas County: Rice ss. Mike Kelso (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God. Signature: [Handwritten Signature]

RECEIVED

DEC 28 2011

KCC WICHITA

AK