

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33999
 Name: LINN Operating, Inc
 Address 1: 600 Travis Ste 5100
 Address 2: _____
 City: Houston State: TX Zip: 77002 + _____
 Contact Person: Rena Carter
 Phone: (405) 241-2223
 Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 095-00432-0000
 Spot Description: KCC
~~SW~~ ~~SE~~ NE SE Sec. 5 Twp. 30 S. R. 8 East West
2310 Feet from North South Line of Section
990 Feet from East West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Kingman
 Lease Name: Pomeroy Unit Well #: 1
 Date Well Completed: 1/15/58
 The plugging proposal was approved on: 6/16/10 (Date)
 by: Jeff Klock (KCC District Agent's Name)
 Plugging Commenced: 11/22/11
 Plugging Completed: 11/23/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	290	N/A
		Production	4 1/2	4344	N/A

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Checked hole, sand at 4180'; bailed 4 sacks cement on sand. Ripped casing at 1990', pipe came free. Pulled up to 1300' & pumped 35 sacks cement, 3%cc & 100# hulls. Pulled to 800' & pumped 35 sacks cement, 3%cc & 100# hulls. Pulled to 340' & circulated with 125 sacks cement to surface. Pulled rest of casing.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc
 Address 1: 190 US Hwy 56 Address 2: _____
 City: Ellinwood State: KS Zip: 67526 + _____
 Phone: (620) 727-3409

Name of Party Responsible for Plugging Fees: LINN Operating, Inc.
 State of Oklahoma County, Oklahoma, ss.
Rena Carter (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Rena Carter

RECEIVED
 JAN 03 2012
 1-3-12
 KCC WICHITA
 AR