

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-20,063-0000

LEASE NAME Schmieg

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 1 TWP. 17S RGE. 28 (N) or (W)

COUNTY Lane

Date Well Completed 9/13/73

Plugging Commenced 5/25/93

Plugging Completed 5/25/93

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? On old form If not, Is well log attached? -

Producing Formation LKC Depth to Top 4081 Bottom 4272 T.D. 4670

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	Oil	4081	4272	8 5/8	286	-0-
				5 1/2	4357	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 4030'. Perf'd 5 1/2" casing @ 1300'. Pumped 200 sxs 60/40 poz w/6% gel down 5 1/2".
Rigged up to annulus and pumped 200 sxs 60/40 poz w/6% gel. SIP 50#. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

MELISSA A MCWHIRT
Notary Public-Oklahoma
TULSA COUNTY
My Commission Expires
March 21, 1994

AND SWORN TO before me this 20th day of July, 19 93

Melissa A. McWhirt

Notary Public

My Commission Expires: March 21, 1994

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

SCHMIEG #1
 SW SW NE, Section 1-17S-28W
 Lane County, Kansas


Commenced: August 9, 1973
 Completed: August 22, 1973

OPERATOR: PATRICK PETROLEUM CO.

15101-20063-0000

Depth From	Depth To	Formation	Remarks
0	70	Surface clay & sand	Ran 7 jts of new 20# 8 5/8" csg.
70	287	Shale & sand	set @ 287' cemented w/175 sks
287	1292	Shale	50/50 Posmix w/3% CC
1292	1570	Shale & sand & redbed	P.D. @ 7 PM 8/9/1973
1570	1602	1st Anhydrite	Cement Circ.
1602	1920	Shale-redbed-sand	
1920	2143	Shale-redbed	
2143	2196	Anhydrite	
2196	2365	Shale-redbed	
2365	2725	Shale	
2725	2904	Shale-lime	
2904	3505	Lime-shale	
3505	3645	Lime	
3645	3914	Lime-shale	
3914	4650	Lime	
4650	4670	Lime & chert	Ran 141 jts of used 14# 5 1/2"
4670	TD		csg. set @ 4359' w/landing jt. cemented w/150 sks Salt Sat Posmix P.D. @ 2:30 AM 8/22/1973

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the SW SW NE, Section 1-17S-28W, Lane County, Kansas, to the best of my knowledge and belief.


 James S. Sutton, II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 24th day of August, 1973, personally appeared James S. Sutton to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.


 Marjorie Hall, Notary Public



RECEIVED
 STATE CORPORATION COMMISSION
 APR 30 1993
 CONSERVATION DIVISION
 Wichita, Kansas