

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-21,244-0000

LEASE NAME Munsel

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

2790 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 1 TWP. 17 RGE. 28 ~~CS~~ or (W)

COUNTY Lane

Date Well Completed 11-10-85

Plugging Commenced 11-11-85

Plugging Completed 11-11-85

LEASE OPERATOR Crane Petroleum, Inc.

ADDRESS Suite 205-A  
5600 S. Syracuse Circle, Englewood, Co. 80110

PHONE#( ) 303-694-1090 OPERATORS LICENSE NO. 4151

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	215	8 5/8	11/2/85	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with 210 sxs 60/40 poz, 6% gel as follows: 50 sxs at 2160'-80 sxs at 1260'; 40 sxs at 240'; 10 sxs on solid bridge at 40'; 15 sxs in rathole, 15 sxs-mousehole. Plug down at 7:45 p.m. on 11/11/85. Job by B.J. Titan, Hays.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF KANSAS COUNTY OF PRATT, ss.

ARNIE LITTLE

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 18th day of Nov., 19 85

Mary L. Tjaden  
Notary Public

My Commission Expires: 3/22/88  
STATE CORPORATION COMMISSION

NOV 20 1985  
11-20-85



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Munsel #1  
 SW SE NE Sec. 1-17S-28W  
 Lane County, Kansas  
 Commenced: 11-2-85  
 Completed: 11-11-85  
 API #15-101-21,244-0000  
 Operator: Crane Petroleum, Inc.

Depth		Formation	Remarks
From	To		
0	69	Clay	Ran 5 joints (205') new, 23#, 8 5/8" casing. Set at 215' with 165 sxs Class A, 2% gel, 3% cc.
69	576	Clay, Shale	Plug down at 8:15 p.m. on 11/2/85. Cement did circulate. Job by B.J. Titan, Great Bend.
576	2022	Sand, Shale	
2022	2513	Lime, Shale	
2513	2920	Shale	
2920	4645	Lime, Shale	
		T.D.	

RTD 4645'

Plugged well with 210 sxs 60/40 poz, 6 % gel as follows: 2160'-50 sxs; 1260'-80 sxs; 240'-40 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; mousehole-15 sxs. Plug down at 7:45 p.m. on 11/11/85. Job by B.J. Titan, Hays. State Plugger was out of Dodge City, Ks.


STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

  
 ARNIE LITTLE, PRESIDENT



  
 NOTARY PUBLIC

My Commission Expires:  
3/22/88

RECEIVED STATE CORPORATION COMMISSION

NOV 20 1985

CONSERVATION DIVISION  
Wichita, Kansas