

API NUMBER 15-101-20,144-00002

LEASE NAME Schneider

WELL NUMBER 1

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 1 TWP. 17S RGE. 28 (N) or (W)

COUNTY Lane

Date Well Completed 3/13/75

Plugging Commenced 5/25/93

Plugging Completed 5/25/93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 491-4314 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? On old form If not, Is well log attached? -

Producing Formation Kansas City Depth to Top 4268 Bottom 4272 T.D. 4350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Kansas City	Oil	4268	72	8 5/8	314	-0-
				5 1/2	4349	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 4030'. Perf'd 5 1/2" casing @ 1300'. Pumped 200 sxs 60/40 poz w/6% gel down 5 1/2". Rigger up to annulus and pumped 200 sxs 60/40 poz w/6% gel. SIP 50#. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 22 1993
 7-22-93
 CONSERVATION DIVISION
 Wichita, Kansas

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

MELISSA A MCWHIRT
 Notary Public-Oklahoma
 TULSA COUNTY SUBSCRIBED
 My Commission Expires
 March 21, 1994

AND SWORN TO before me this 20th day of July, 19 93

Melissa A McWhirt
 Notary Public

My Commission Expires: March 21, 1994