

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas, 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

15/01 205280000

Give All Information Completely
Make Required Affidavit

COUNTY _____ Lape SEC. 5 TWP. 17 RGE. 28W E/W
Location as in quarters or footage from lines:
C of SW1/4

Lease Owner Mesquite Production & Exploration
Lease Name Schmieg #1 Well No. _____
Office Address P.O. Box 79646 Houston, Texas 77079
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 6-20-83
Plugging completed 6-23-83
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Plat.

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D.4450'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	309'	none
				4-1/2"	4427'	1015'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 4080' and ran 4 sacks cement. Shot casing @3600'
2010', 1215', 1010' and pulled a total of 25 joints (1015') of 4-1/2" casing.

Plugged well with 3 sacks hulls, 10 sacks gel, 70 sacks cement, 15 sacks gel,
1 sack hulls, released plug and displaced with 150 sacks cement.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature)

R. Darrell Kelso
Box 347 Chase, Ks. 67524

My Commission expires: My Comm. Exp. Aug. 15, 1985



Irene Hoover
RECEIVED
STATE CORPORATION COMMISSION

JUN 27 1983
6-27-83
REGISTRATION DIVISION
Wichita, Kansas