

State of Kansas



15-203-30054-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

WICHITA, KANSAS 67202

RECEIVED
CORPORATION COMMISSION

OCT 17 1966

10-17-1964

CONSERVATION DIVISION
Wichita, Kansas

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Dale Oller of Murfin Drilling Co., has this

date requested permission to plug the following described well:

Mull Drlg. Co.

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Incorporated,

Complete Address: 1625 Wichita, Plaza, Wichita, Kansas.

Lease Name: Boland Well No. 1

Location: SE-NW-NW Sec. 14 Twp. 20 Rge. (E)(W) 36

County Wichita Total Depth 5200 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oller was instructed to plug the well as follows:

355'--8 5/8" Surface pipe, cement circulated with -- Sx.

Circulate hole with heavy mud, set plug @ 660' and 25 Sx. cement.

"	"	330'	with $\frac{1}{4}$ sk. hulls &
			20 Sx. cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls &
			10 Sx. cement.

Very truly yours,

A. L. Nichols

Conservation Division Agent