



15-203-20023-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1974
02-19-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clarence Michael of Sage Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Michael guarantees payment of the plugging fee.

Operator's full Name: Maurice L. Brown Trust & I. W. Woolsey.

Complete Address: 1500 Vickers KSB&T Building, Wichita, Kansas.

Lease Name: G. S. Smith Well No. F-1

Location: CSW-SW Sec. 4 Twp. 20 Rge. (E)(W) 36

County: Wichita Total Depth 5250' Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Michael was instructed to plug the well as follows:

285'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 675'.

Circulate hole with heavy mud. Pull DP to 900' and displace 110 Cu. Ft. cement thru DP. Pull DP to 300' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols

Conservation Division Agent