

State of Kansas



15-171-20064-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSIONMAY 31 1974
05-31-1974
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sam Wagner of Rains & Williamson Oil Co., has this
date requested permission to plug the following described well:Mr. Wagner guarantees payment of the plugging fee.Operator's full Name: Thunderbird Drilling, Incorporated,Complete Address: P. O. Box #18407, Wichita, Kansas.Lease Name: Huck Well No. A-1Location: CSW-SW Sec. 36 Twp. 17 Rge. (E)(W) 32County: Scott Total Depth Oil WellGas Well Input Well SWD Well D & A X Lost HoleMr. Wagner was instructed to plug the well as follows:605'--8 5/8" Surface casing, cement circulated with 320 Sx.Top of Dakota section @ 1025'.Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 620' and displace 30 Cu. Ft. cement thru DP
from 620' to 550'. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10
Cu. Ft. cement to bottom of cellar.

Very truly yours,

 Conservation Division Agent