



15-171-30058-00-00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 17 1965  
11-17-1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Herb Morrell of Earl F. Wakefield has this

date requested permission to plug the following described well:  
Cimarron Expl., Inc.

Mr. Morrell guarantees payment of the plugging fee.

Operator's full Name: Cimarron Exploration, Incorporated,

Complete Address: Box # 1142, Liberal, Kansas.

Lease Name: Crowell Well No. 1

Location: NE-NE-NE Sec. 35 Twp. 17 Rge. (E)(W) 32

County Scott Total Depth 4403 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Morrell was instructed to plug the well as follows:

242'--8 5/8" Surface pipe, cement circulated with 250 Sx.

Circulate hole with heavy mud, set plug @ 660' and 20 Sx. cement.

"	"	240' with 1/2 sk. hulls &
		20 Sx. cement.
"	"	40' with 1/2 sk. hulls &
		10 Sx. cement.

Very truly yours,

W. L. Dike  
Conservation Division Agent