

State of Kansas



15-171-20072-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSIONNOV 27 1974
11-27-1974
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Oden of Red Tiger Drilling Company has this
date requested permission to plug the following described well:Mr. Oden guarantees payment of the plugging fee.Operator's full Name: Okmar Oil Company,Complete Address: 1130 Vickers KSB&T Building, Wichita, Kansas.Lease Name: Krupp Well No. 1Location: CNW-SW Sec. 25 Twp. 17 Rge. (E)(W)32County: Scott Total Depth 4648' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Oden was instructed to plug the well as follows:315'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1050'.Circulate hole with heavy mud. Pull DP to 1275' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 315' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent